## Universal Serial Bus Mass Storage Class

**Bulk-Only Transport** 

Revision 1.0 September 31, 1999

### **Change History**

Revision	Issue Date	Comments
0.7	September 23, 1998	Initial draft, pre-release
0.8	October 6, 1998	Revisions made at the Mass Storage DWG review – Irvine, CA
0.9	October 21, 1998	Revisions made at the Mass Storage DWG review – Plano, TX
0.9a	January 5, 1999	Revisions made at the Mass Storage DWG review – Tigard, OR
0.9b	February 1, 1999	Additions of LUN support - Milpitas, CA
1.0[RC1]	March 5, 1999	RR review - Midway, UT
1.0[RC2]	March 23, 1999	Revisions from reflector review comments
1.0[RC3]	March 29, 1999	Specification line by line review – Milpitas, CA
1.0[RC4]	June 21, 1999	Specification line by line review – RR21 – Milpitas, CA
1.0	September 31, 1999	Final Revision edits for Released Document – SLC, UT

USB Device Class Definition for Mass Storage Devices Copyright © 1998, 1999, USB Implementers Forum. All rights reserved.

#### INTELLECTUAL PROPERTY DISCLAIMER

THIS SPECIFICATION IS PROVIDED "AS IS" WITH NO WARRANTIES WHATSOEVER INCLUDING ANY WARRANTY OF MERCHANTABILITY, FITNESS FOR ANY PARTICULAR PURPOSE, OR ANY WARRANTY OTHERWISE ARISING OUT OF ANY PROPOSAL, SPECIFICATION, OR SAMPLE. A LICENSE IS HEREBY GRANTED TO REPRODUCE AND DISTRIBUTE THIS SPECIFICATION FOR INTERNAL USE ONLY. NO OTHER LICENSE, EXPRESS OR IMPLIED, BY ESTOPPEL OR OTHERWISE, TO ANY OTHER INTELLECTUAL PROPERTY RIGHTS IS GRANTED OR INTENDED HEREBY. AUTHORS OF THIS SPECIFICATION DISCLAIM ALL LIABILITY, INCLUDING LIABILITY FOR INFRINGEMENT OF PROPRIETARY RIGHTS, RELATING TO IMPLEMENTATION OF INFORMATION IN THIS SPECIFICATION. AUTHORS OF THIS SPECIFICATION ALSO DO NOT WARRANT OR REPRESENT THAT SUCH IMPLEMENTATION(S) WILL NOT INFRINGE SUCH RIGHTS.

#### Contributors

Al Rickey, Phoenix Technologies Alan Haffner. Lexar Media Bill Stanley, Adaptec Calaimany Bhoopathi, Shuttle Technology Curtis E. Stevens, Phoenix Technologies Darrell Redford, Iomega Corporation Dave Gilbert, In-System Design David G. Lawrence, Global Technology Development David L. Jolley, Iomega Corporation David Luke, In-System Design Eric Luttman, In-System Design Glen Slick, Microsoft Corporation Hiromichi Oribe, Hagiwara Sys-ComCo Jan Matejica, PIMC/Philips Jim Blackson, Y-E Data, Inc Jim Quigley, Iomega Corporation Johan Craeybeckk, PIMC/Philips Jordan Brown, Sun Microsystems Kenny Chu, Hagiwara Sys-ComCo Kenichi Hamada, Y-E Data, Inc Mark Williams, Microsoft Corporation Masayuki Kitagawa, Mitsumi Mike Chen, CMD Technology

Mike Glass, Microsoft Corporation Mike Liebow, eTEK Labs Mike Nguyen, TEAC Mike Poulsen, Iomega Corporation Moto Watanabe, Hagiwara N.R. Devanathan, Shuttle Technology Paramita Das, Sun Microsystems Pat LaVarre, Iomega Corporation Peter S'Heeren, PIMC/Philips Ryota Okazaki, NEC Corporation Sadao Yabuki, TEAC Shigeyoshi Hashi, NEC Corporation Shing F. Lin, Adaptec Steve Bayless, Hewlett-Packard Steve Kolokowsky, Anchor Chips Steven Smith, eTEK Labs Terry Moore, MCCI Tim Bradshaw, Iomega Corp Toyoko Shimizu, Y-E Data, Inc Trenton Henry, SMSC Troy Davidson, Iomega Corporation Tsuyoshi Osawa, TEAC Yuji Oishi, Hagiwara Sys-Com Co Ltd

## **Table of Contents**

1	Specification Overview and Scope	. 5
_	1	
2		
	2.1 Conventions	
	2.2 Definitions	
3		
	3.1 Bulk-Only Mass Storage Reset ( <i>class-specific request</i> )	
	3.2 Get Max LUN ( <i>class-specific request</i> )	
	3.3 Host/Device Packet Transfer Order	
	3.4 Command Queuing	
	3.5 Bi-Directional Command Protocol	
4	Standard Descriptors	. 9
	4.1 Device Descriptor	9
	4.1.1 Serial Number	
	4.1.2 Valid Serial Number Characters	10
	4.2 Configuration Descriptor	
	4.3 Interface Descriptors	
	4.4 Endpoint Descriptors	
	4.4.1 Bulk-In Endpoint	
	4.4.2 Bulk-Out Endpoint	12
5	Command/Data/Status Protocol	13
	5.1 Command Block Wrapper (CBW)	13
	5.2 Command Status Wrapper (CSW)	14
	5.3 Data Transfer Conditions	15
	5.3.1 Command Transport	15
	5.3.2 Data Transport	15
	5.3.3 Status Transport	16
	5.3.4 Reset Recovery	16
6	Host/Device Data Transfers	17
	6.1 Overview	
	6.2 Valid and Meaningful CBW	17
	6.2.1 Valid CBW	17
	6.2.2 Meaningful CBW	17
	6.3 Valid and Meaningful CSW	17
	6.3.1 Valid CSW	17
	6.3.2 Meaningful CSW	17
	6.4 Device Error Handling	
	6.5 Host Error Handling	
	6.6 Error Classes	
	6.6.1 CBW Not Valid	
	6.6.2 Internal Device Error	
	6.6.3 Host/Device Disagreements	
	6.6.4 Command Failure	
	6.7 The Thirteen Cases	
	6.7.1 Hn - Host expects no data transfers	
	6.7.2 Hi - Host expects to receive data from the device	
	6.7.3 Ho - Host expects to send data to the device	21

## List of Tables

Table 3.1 – Bulk-Only Mass Storage Reset	7
Table 3.2 –Get Max LUN	
Table 4.1 - Device Descriptor	9
Table 4.2 - Example Serial Number Format	
Table 4.3 - Valid Serial Number Characters	
Table 4.4 - Configuration Descriptor	10
Table 4.5 – Bulk-Only Data Interface Descriptor	11
Table 4.6 - Bulk-In Endpoint Descriptor	
Table 4.7 – Bulk-Out Endpoint Descriptor	12
Table 5.1 - Command Block Wrapper	13
Table 5.2 - Command Status Wrapper	14
Table 5.3 - Command Block Status Values	
Table 6.1 - Host/Device Data Transfer Matrix	19

## **List of Figures**

Figure 1 - Command/Data/Status Flow	
Figure 2 - Status Transport Flow	15

## 1 Specification Overview and Scope

#### 1.1 Scope

A familiarity with the USB 1.0 and 1.1 Specifications and the USB Mass Storage Class Specification Overview is assumed.

This specification addresses Bulk-Only Transport, or in other words, transport of command, data, and status occurring solely via Bulk endpoints (not via Interrupt or Control endpoints). This specification only uses the default pipe to clear a STALL condition on the Bulk endpoints and to issue class-specific requests as defined below. This specification does not require the use of an Interrupt endpoint.

This specification defines support for logical units that share common device characteristics. Although this feature provides the support necessary to allow like mass storage devices to share a common USB interface descriptor, it is not intended to be used to implement interface bridge devices.

## 2 Terms and Abbreviations

#### 2.1 Conventions

Numbers without annotation are decimal	1, 17, 23
Hexadecimal numbers are followed by an 'h'	1Fh, FCh, 38h
Binary numbers are followed by a 'b'	011b, 101b, 01110010b
Words in <i>italics</i> indicate terms defined by USB or by this specification	bRequest, dCSWTag

#### 2.2 Definitions

#### **Command Block Wrapper (CBW)**

A packet containing a command block and associated information.

#### **Command Status Wrapper (CSW)**

A packet containing the status of a command block.

#### Data-In

Indicates a transfer of data IN from the device to the host.

#### Data-Out

Indicates a transfer of data OUT from the host to the device.

#### **Device Request**

Requests from the host to the device using the default pipe.

#### Phase Error

An error returned by the device indicating that the results of processing further CBWs will be indeterminate until the device is reset.

#### Processed

Data received and controlled internally by the device to the point that the host need no longer be concerned about it.

#### Relevant

The amount of the data sent to the host by the device that is significant.

#### **Reset Recovery**

An error recovery procedure by which the host prepares the device for further CBWs.

#### **Thin Diagonal**

Cases where the host and device are in complete agreement about the data transfer. See Chapter 6 - Host/Device Data Transfers, for additional information regarding error cases and the "thin diagonal."

## **3** Functional Characteristics

#### 3.1 Bulk-Only Mass Storage Reset (class-specific request)

This request is used to reset the mass storage device and its associated interface.

This class-specific request shall ready the device for the next CBW from the host.

The host shall send this request via the default pipe to the device. The device shall preserve the value of its bulk data toggle bits and endpoint STALL conditions despite the Bulk-Only Mass Storage Reset.

The device shall NAK the status stage of the device request until the Bulk-Only Mass Storage Reset is complete.

To issue the Bulk-Only Mass Storage Reset the host shall issue a device request on the default pipe of:

- *bmRequestType*: Class, Interface, host to device
- *bRequest* field set to 255 (FFh)
- *wValue* field set to 0
- *wIndex* field set to the interface number
- *wLength* field set to 0

#### Table 3.1 – Bulk-Only Mass Storage Reset

bmRequestType	bRequest	wValue	wIndex	wLength	Data
00100001b	11111111b	0000h	Interface	0000h	none

#### **3.2 Get Max LUN** (class-specific request)

The device *may* implement several logical units that share common device characteristics. The host uses bCBWLUN (see 5.1 Command Block Wrapper (CBW)) to designate which logical unit of the device is the destination of the CBW. The Get Max LUN device request is used to determine the number of logical units supported by the device. Logical Unit Numbers on the device shall be numbered contiguously starting from LUN 0 to a maximum LUN of 15 (Fh).

To issue a Get Max LUN device request, the host shall issue a device request on the default pipe of:

- *bmRequestType*: Class, Interface, device to host
- *bRequest* field set to 254 (FEh)
- *wValue* field set to 0
- *wIndex* field set to the interface number
- *wLength* field set to 1

Table 3.2 –Get Max LUN

bmRequestType	bRequest	wValue wIndex		wLength	Data
10100001b	11111110b	0000h	Interface	0001h	1 byte

The device shall return one byte of data that contains the maximum LUN supported by the device. For example, if the device supports four LUNs then the LUNs would be numbered from 0 to 3 and the return value would be 3. If no LUN is associated with the device, the value returned shall be 0. The host shall not send a command block wrapper (CBW) to a non-existing LUN.

Devices that do not support multiple LUNs may STALL this command.

#### 3.3 Host/Device Packet Transfer Order

The host shall send the CBW before the associated Data-Out, and the device shall send Data-In after the associated CBW and before the associated CSW. The host *may* request Data-In or CSW before sending the associated CBW.

If the *dCBWDataTransferLength* is zero, the device and the host shall transfer no data between the CBW and the associated CSW.

#### 3.4 Command Queuing

The host shall not transfer a CBW to the device until the host has received the CSW for any outstanding CBW. If the host issues two consecutive CBWs without an intervening CSW or reset, the device response to the second CBW is indeterminate.

#### 3.5 **Bi-Directional Command Protocol**

This specification does not provide for bi-directional data transfer in a single command.

## **4** Standard Descriptors

The device shall support the following standard USB descriptors:

- Device. Each USB device has one device descriptor (per USB Specification).
- **Configuration**. Each USB device has one default configuration descriptor, which supports at least one interface.
- **Interface**. The device shall support at least one interface, known herein as the Bulk-Only Data Interface. Some devices *may* support additional interfaces, to provide other capabilities.
- **Endpoint**. The device shall support the following endpoints, in addition to the default pipe that is required of all USB devices:
  - (a) Bulk-In endpoint
  - (b) Bulk-Out endpoint

Some devices *may* support additional endpoints, to provide other capabilities. The host shall use the first reported Bulk-In and Bulk-Out endpoints for the selected interface.

• String. The device shall supply a unique serial number as detailed in 4.1.1 - Serial Number.

This specification defines no class-specific descriptors.

The rest of this section describes the standard USB device, configuration, interface, endpoint, and string descriptors for the device. For superseding information about these and other standard descriptors, see Chapter 9, "USB Device Framework," of the *USB Specification*.

#### 4.1 Device Descriptor

Each USB device has one device descriptor (per *USB Specification*). The device shall specify the device class and subclass codes in the interface descriptor, and not in the device descriptor.

Offset	Field	Size	Value	Description
0	bLength	Byte	12h	Size of this descriptor in bytes.
1	bDescriptorType	Byte	01h	DEVICE descriptor type.
2	bcdUSB	Word	????h	USB Specification Release Number in Binary-Coded Decimal
				(i.e. $2.10 = 210h$ ). This field identifies the release of the USB
				Specification with which the device and is descriptors are
				compliant.
4	bDeviceClass	Byte	00h	Class is specified in the interface descriptor.
5	bDeviceSubClass	Byte	00h	Subclass is specified in the interface descriptor.
6	bDeviceProtocol	Byte	00h	Protocol is specified in the interface descriptor.
7	bMaxPacketSize0	Byte	??h	Maximum packet size for endpoint zero. (only 8, 16, 32, or 64
				are valid (08h, 10h, 20h, 40h)).
8	idVendor	Word	????h	Vendor ID (assigned by the USB-IF).
10	idProduct	Word	????h	Product ID (assigned by the manufacturer).
12	bcdDevice	Word	????h	Device release number in binary-coded decimal.
14	iManufacturer	Byte	??h	Index of string descriptor describing the manufacturer.
15	iProduct	Byte	??h	Index of string descriptor describing this product.
16	iSerialNumber	Byte	??h	Index of string descriptor describing the device's serial number.
				(Details in 4.1.1 below)
17	<b>bNumConfigurations</b>	Byte	??h	Number of possible configurations.

**Table 4.1 - Device Descriptor** 

NOTE: Information in this table is from the *USB Specification version 1.1 table 9-7*. **Bold text** has been added for clarifications when using these descriptors with this specification.

#### 4.1.1 Serial Number

The *iSerialNumber* field shall be set to the index of the string descriptor that contains the serial number. The serial number shall contain at least 12 valid digits, represented as a UNICODE string. The last 12 digits of the serial number shall be unique to each USB *idVendor* and *idProduct* pair.

The host *may* generate a globally unique identifier by concatenating the 16 bit *idVendor*, the 16 bit *idProduct* and the value represented by the last 12 characters of the string descriptor indexed by *iSerialNumber*.

The field *iSerialNumber* is an index to a string descriptor and does not contain the string itself. An example format for the String descriptor is shown below.

Offset	Field	Size	Value	Description	
0	bLength	Byte	??h	Size of this descriptor in bytes - Minimum of 26 (1Ah)	
1	bDescriptorType	Byte	03h	STRING descriptor type	
2	wString1	Word	00??h	Serial number character 1	
4	wString2	Word	00??h	Serial number character 2	
6	wString3	Word	00??h	Serial number character 3	
:	:	Word	:	:	
:	:	Word	:	:	
n x 2	wStringn	Word	00??h	Serial number character n	
	Shall be at least 12 characters long				

 Table 4.2 - Example Serial Number Format

#### 4.1.2 Valid Serial Number Characters

The following table defines the valid characters that the device shall use for the serial number.

#### Table 4.3 - Valid Serial Number Characters

Numeric	ASCII
0030h through 0039h	"0" through "9"
0041h through 0046h	"A" through "F"

#### 4.2 Configuration Descriptor

 Table 4.4 - Configuration Descriptor

Offset	Field	Size	Value	Description	
0	bLength	Byte	09h	Size of this descriptor in bytes.	
1	bDescriptorType	Byte	02h	CONFIGURATION Descriptor Type.	
2	wTotalLength	Word	????h	Total length of data returned for this configuration. Includes the combined length of all descriptors (configuration, interface, endpoint, and class- or vendor-specific) returned for this configuration.	
4	bNumInterfaces	Byte	??h	Number of interfaces supported by this configuration. The device shall support at least the Bulk-Only Data Interface.	
5	bConfigurationValue	Byte	??h	Value to use as an argument to the <i>SetConfiguration()</i> request to select this configuration.	
6	iConfiguration	Byte	??h	Index of string descriptor describing this configuration.	
7	bmAttributes	Byte	?0h	Bit       Description         7       Reserved (set to one)         6       Self-powered         5       Remote Wakeup         40       Reserved (reset to zero)         Bit 7 is reserved and must be set to one for historical reasons.         For a full description of this bmAttributes bitmap, see the USB 1.1 Specification.	
8	MaxPower	Byte	??h	Maximum power consumption of the USB device from the bus in this specific configuration when the device is fully operational. Expressed in 2mA units (i.e. 50 = 100mA)	

NOTE: Information in this table is from the *USB Specification version 1.1 table 9-8*. **Bold text** has been added for clarifications when using these descriptors with this specification.

#### 4.3 Interface Descriptors

The device shall support at least one interface, known herein as the Bulk-Only Data Interface. The Bulk-Only Data Interface uses three endpoints.

Composite mass storage devices *may* support additional interfaces, to provide other features such as audio or video capabilities. This specification does not define such interfaces.

The interface *may* have multiple alternate settings. The host shall examine each of the alternate settings to look for the *bInterfaceProtocol* and *bInterfaceSubClass* it supports optimally.

Offset	Field	Size	Value	Description
0	bLength	Byte	09h	Size of this descriptor in bytes.
1	bDescriptorType	Byte	04h	INTERFACE Descriptor Type.
2	bInterfaceNumber	Byte	0?h	Number of interface. Zero-based value identifying the index in the array of concurrent interfaces supported by this configuration.
3	bAlternateSetting	Byte	??h	Value used to select alternate setting for the interface identified in the prior field.
4	bNumEndpoints	Byte	??h	Number of endpoints used by this interface (excluding endpoint zero). This value shall be at least 2.
5	bInterfaceClass	Byte	08h	MASS STORAGE Class.
6	bInterfaceSubClass	Byte	0?h	Subclass code (assigned by the USB-IF). Indicates which industry standard command block definition to use. Does not specify a type of storage device such as a floppy disk or CD-ROM drive. (See USB Mass Storage Overview Specification)
7	bInterfaceProtocol	Byte	50h	BULK-ONLY TRANSPORT. (See USB Mass Storage Overview Specification)
8	iInterface	Byte	??h	Index to string descriptor describing this interface.

 Table 4.5 – Bulk-Only Data Interface Descriptor

NOTE: Information in this table is from the USB Specification version 1.1 table 9-9. Bold text has been added for clarifications when using these descriptors with this specification.

#### 4.4 Endpoint Descriptors

The device shall support at least three endpoints: Control, Bulk-In and Bulk-Out.

Each USB device defines a Control endpoint (Endpoint 0). This is the default endpoint and does not require a descriptor.

#### 4.4.1 Bulk-In Endpoint

The Bulk-In endpoint is used for transferring data and status from the device to the host.

 Table 4.6 - Bulk-In Endpoint Descriptor

Offset	Field	Size	Value	Description
0	bLength	Byte	07h	Size of this descriptor in bytes.
1	bDescriptorType	Byte	05h	ENDPOINT Descriptor Type.
2	bEndpointAddress	Byte	8?h	The address of this endpoint on the USB device. The address is
				encoded as follows.
				Bit Description
				30 The endpoint number
				64 Reserved, set to 0
				7   1 = In
3	bmAttributes	Byte	02h	This is a Bulk endpoint.
4	wMaxPacketSize	Word	00??h	Maximum packet size. Shall be 8, 16, 32 or 64 bytes (08h,
				10h, 20h, 40h).
6	bInterval	Byte	00h	Does not apply to Bulk endpoints.

#### 4.4.2 Bulk-Out Endpoint

The Bulk-Out endpoint is used for transferring command and data from the host to the device.

Offset	Field	Size	Value	Description		
0	bLength	Byte	07h	Size of this descriptor in bytes.		
1	bDescriptorType	Byte	05h	ENDPOINT descriptor type.		
2	bEndpointAddress	Byte	0?h	The address of this endpoint on the USB device. This address is encoded as follows: $     \begin{array}{c} \underline{Bit} \\ \overline{30} \\ \overline{64} \\ 7 \\ 0 = Out \end{array}     \begin{array}{c} \underline{Description} \\ \overline{64} \\ 0 = Out \end{array} $		
3	bmAttributes	Byte	02h	This is a Bulk endpoint.		
4	wMaxPacketSize	Word	00??h	Maximum packet size. Shall be 8, 16, 32 or 64 bytes (08h, 10h, 20h, or 40h).		
6	bInterval	Byte	00h	Does not apply to Bulk endpoints.		

#### Table 4.7 – Bulk-Out Endpoint Descriptor

## 5 Command/Data/Status Protocol

Figure 1 - Command/Data/Status Flow shows the flow for Command Transport, Data-In, Data-Out and Status Transport. The following sections define Command and Status Transport. Figure 2 - Status Transport Flow shows a detailed diagram of Status Transport. The following sections outline the various conditions for host/device communication, possible errors, and recovery procedures.

#### 5.1 Command Block Wrapper (CBW)

The CBW shall start on a packet boundary and shall end as a short packet with exactly 31 (1Fh) bytes transferred. Fields appear aligned to byte offsets equal to a multiple of their byte size. All subsequent data and the CSW shall start at a new packet boundary. All CBW transfers shall be ordered with the LSB (byte 0) first (little endian). Refer to the *USB Specification* Terms and Abbreviations for clarification.




Figure 1 - Command/Data/Status Flow

bit Byte	7	6	5	4	3	2	1	0	
0-3	dCBWSignature								
4-7		dCBWTag							
<b>8-11</b> (08h-0Bh)		dCBWDataTransferLength							
12 (0Ch)	bmCBWFlags								
13 (0Dh)	Reserved (0) bCBWLUN								
14 (0Eh)	Reserved (0) <i>bCBWCBLength</i>								
<b>15-30</b> (0Fh-1Eh)	CBWCB								

#### Table 5.1 - Command Block Wrapper

#### dCBWSignature:

Signature that helps identify this data packet as a CBW. The signature field shall contain the value 43425355h (little endian), indicating a CBW.

#### dCBWTag:

A Command Block Tag sent by the host. The device shall echo the contents of this field back to the host in the *dCSWTag* field of the associated CSW. The *dCSWTag* positively associates a CSW with the corresponding CBW.

#### dCBWDataTransferLength:

The number of bytes of data that the host expects to transfer on the Bulk-In or Bulk-Out endpoint (as indicated by the *Direction* bit) during the execution of this command. If this field is zero, the device and the host shall transfer no data between the CBW and the associated CSW, and the device shall ignore the value of the *Direction* bit in *bmCBWFlags*.

#### bmCBWFlags:

The bits of this field are defined as follows:

Bit 7	Direction - the device shall ignore this bit if the dCBWDataTransferLength field is
	zero, otherwise:

0 = Data-Out from host to the device,

- 1 = Data-In from the device to the host.
- Bit 6 Obsolete. The host shall set this bit to zero.

Bits 5..0 Reserved - the host shall set these bits to zero.

#### bCBWLUN:

The device Logical Unit Number (LUN) to which the command block is being sent. For devices that support multiple LUNs, the host shall place into this field the LUN to which this command block is addressed. Otherwise, the host shall set this field to zero.

#### bCBWCBLength:

The valid length of the *CBWCB* in bytes. This defines the valid length of the command block. The only legal values are 1 through 16 (01h through 10h). All other values are reserved.

#### CBWCB:

The command block to be executed by the device. The device shall interpret the first *bCBWCBLength* bytes in this field as a command block as defined by the command set identified by *bInterfaceSubClass*. If the command set supported by the device uses command blocks of fewer than 16 (10h) bytes in length, the significant bytes shall be transferred first, beginning with the byte at offset 15 (Fh). The device shall ignore the content of the *CBWCB* field past the byte at offset (15 + bCBWCBLength - 1).

#### 5.2 Command Status Wrapper (CSW)

The CSW shall start on a packet boundary and shall end as a short packet with exactly 13 (0Dh) bytes transferred. Fields appear aligned to byte offsets equal to a multiple of their byte size. All CSW transfers shall be ordered with the LSB (byte 0) first (little endian). Refer to the *USB Specification* Terms and Abbreviations for clarification.

bit Byte	7	6	5	4	3	2	1	0
0-3		dCSWSignature						
4-7		dCSWTag						
<b>8-11</b> (8-Bh)		dCSWDataResidue						
12 (Ch)	bCSWStatus							

**Table 5.2 - Command Status Wrapper** 

#### dCSWSignature:

Signature that helps identify this data packet as a CSW. The signature field shall contain the value 53425355h (little endian), indicating CSW.

#### dCSWTag:

The device shall set this field to the value received in the *dCBWTag* of the associated CBW.

#### dCSWDataResidue:

For Data-Out the device shall report in the *dCSWDataResidue* the difference between the amount of data expected as stated in the *dCBWDataTransferLength*, and the actual amount of data processed by the device. For Data-In the device shall report in the *dCSWDataResidue* the difference between the amount of data expected as stated in the *dCBWDataTransferLength* and the actual amount of relevant data sent by the device. The *dCSWDataResidue* shall not exceed the value sent in the *dCBWDataTransferLength*.

#### bCSWStatus:

*bCSWStatus* indicates the success or failure of the command. The device shall set this byte to zero if the command completed successfully. A non-zero value shall indicate a failure during command execution according to the following table:

Value	Description	
00h	Command Passed ("good status")	
01h Command Failed		
02h	Phase Error	
03h and 04h	Reserved (Obsolete)	
05h to FFh	Reserved	

**Table 5.3 - Command Block Status Values** 

#### **5.3 Data Transfer Conditions**

This section describes how the host and device remain synchronized.

The host indicates the expected transfer in the CBW using the *Direction* bit and the

*dCBWDataTransferLength* field. The device then determines the actual direction and data transfer length. The device responds as defined in 6 - Host/Device Data Transfers by transferring data, STALLing endpoints when specified, and returning the appropriate CSW.

#### 5.3.1 Command Transport

The host shall send each CBW, which contains a command block, to the device via the Bulk-Out endpoint. The CBW shall start on a packet boundary and end as a short packet with exactly 31 (1Fh) bytes transferred.

The device shall indicate a successful transport of a CBW by accepting (ACKing) the CBW. If the CBW is not valid see 6.6.1 - CBW Not Valid. If the host detects a STALL of the Bulk-Out endpoint during command transport, the host shall respond with a Reset Recovery (see 5.3.4 - Reset Recovery).

#### 5.3.2 Data Transport

All data transport shall begin on a packet boundary.

The host shall attempt to transfer the exact number of bytes to or from the device as specified by the *dCBWDataTransferLength* and the *Direction* bit. The device shall respond as specified in 6 - Host/Device Data Transfers.




Figure 2 - Status Transport Flow

To report an error before data transport completes and to maximize data integrity, the device *may* terminate the command by STALLing the endpoint in use (the Bulk-In endpoint during data in, the Bulk-Out endpoint during data out).

#### 5.3.3 Status Transport

The device shall send each CSW to the host via the Bulk-In endpoint. The CSW shall start on a packet boundary and end as a short packet with exactly 13 (Dh) bytes transferred. Figure 2 - Status Transport Flow defines the algorithm the host shall use for any CSW transfer.

The CSW indicates to the host the status of the execution of the command block from the corresponding CBW. The *dCSWDataResidue* field indicates how much of the data transferred is to be considered processed or relevant. The host shall ignore any data received beyond that which is relevant.

#### 5.3.3.1 Phase Error

The host shall perform a Reset Recovery when Phase Error status is returned in the CSW.

#### 5.3.4 Reset Recovery

For Reset Recovery the host shall issue in the following order: :

- (a) a Bulk-Only Mass Storage Reset
- (b) a *Clear Feature HALT* to the Bulk-In endpoint
- (c) a *Clear Feature HALT to* the Bulk-Out endpoint

## 6 Host/Device Data Transfers

#### 6.1 Overview

A Bulk-Only Protocol transaction begins with the host sending a CBW to the device and attempting to make the appropriate data transfer (In, Out or none). The device receives the CBW, checks and interprets it, attempts to satisfy the host's request, and returns status via a CSW. This section describes in more detail this interaction between the host and the device during normal and abnormal Bulk-Only Protocol transactions.

#### 6.2 Valid and Meaningful CBW

The host communicates its intent to the device through the CBW. The device performs two verifications on every CBW received. First, the device verifies that what was received is a valid CBW. Next, the device determines if the data within the CBW is meaningful.

The device shall not use the contents of the *dCBWTag* in any way other than to copy its value to the *dCSWTag* of the corresponding CSW.

#### 6.2.1 Valid CBW

The device shall consider the CBW valid when:

- The CBW was received after the device had sent a CSW or after a reset,
- the CBW is 31 (1Fh) bytes in length,
- and the *dCBWSignature* is equal to 43425355h.

#### 6.2.2 Meaningful CBW

The device shall consider the contents of a valid CBW meaningful when:

- no reserved bits are set,
- the *bCBWLUN* contains a valid LUN supported by the device,
- and both *bCBWCBLength* and the content of the *CBWCB* are in accordance with *bInterfaceSubClass*.

#### 6.3 Valid and Meaningful CSW

The device generally communicates the results of its attempt to satisfy the host's request through the CSW. The host performs two verifications on every CSW received. First, the host verifies that what was received is a valid CSW Next, the host determines if the data within the CSW is meaningful.

#### 6.3.1 Valid CSW

The host shall consider the CSW valid when:

- the CSW is 13 (Dh) bytes in length,
- and the *dCSWSignature* is equal to 53425355h,
- the *dCSWTag* matches the *dCBWTag* from the corresponding CBW.

#### 6.3.2 Meaningful CSW

The host shall consider the contents of the CSW meaningful when:

- either the *bCSWStatus* value is 00h or 01h and the *dCSWDataResidue* is less than or equal to *dCBWDataTransferLength*..
- or the *bCSWStatus* value is 02h.

#### 6.4 Device Error Handling

The device may not be able to fully satisfy the host's request. At the point when the device discovers that it cannot fully satisfy the request, there may be a Data-In or Data-Out transfer in progress on the bus, and the host may have other pending requests. The device *may* cause the host to terminate such transfers by STALLing the appropriate pipe.

The response of a device to a CBW that is not meaningful is not specified.

Please note that whether or not a STALL handshake actually appears on the bus depends on whether or not there is a transfer in progress at the point in time when the device is ready to STALL the pipe.

#### 6.5 Host Error Handling

If the host receives a CSW which is not valid, then the host shall perform a Reset Recovery. If the host receives a CSW which is not meaningful, then the host *may* perform a Reset Recovery.

#### 6.6 Error Classes

In every transaction between the host and the device, there are four possible classes of errors. These classes are not always independent of each other and may occur at any time during the transaction.

#### 6.6.1 CBW Not Valid

If the CBW is not valid, the device shall STALL the Bulk-In pipe. Also, the device shall either STALL the Bulk-Out pipe, or the device shall accept and discard any Bulk-Out data. The device shall maintain this state until a Reset Recovery.

#### 6.6.2 Internal Device Error

The device may detect an internal error for which it has no reliable means of recovery other than a reset. The device shall respond to such conditions by:

- either STALLing any data transfer in progress and returning a Phase Error status (*bCSWStatus* = 02h).
- or STALLing all further requests on the Bulk-In and the Bulk-Out pipes until a Reset Recovery.

#### 6.6.3 Host/Device Disagreements

After recognizing that a CBW is valid and meaningful, and in the absence of internal errors, the device may detect a condition where it cannot meet the host's expectation for data transfer, as indicated by the *Direction* bit of the *bmCBWFlags* field and the *dCBWDataTransferLength* field of the CBW. In some of these cases, the device may require a reset to recover. In these cases, the device shall return Phase Error status (*bCSWStatus* = 02h). Details on which cases result in Phase Error vs. non-Phase Error status are given in 6.7 The Thirteen Cases.

#### 6.6.4 Command Failure

After recognizing that a CBW is valid and meaningful, the device may still fail in its attempt to satisfy the command. The device shall report this condition by returning a Command Failed status (bCSWStatus = 01h).

#### 6.7 The Thirteen Cases

This section describes the thirteen possible cases of host expectations and device intent in the absence of overriding error conditions. Table 6.1 - Host/Device Data Transfer Matrix graphically displays these thirteen cases.

Important notes about the thirteen cases.

- Cases (1), (6) and (12) represent the majority of host and device transactions. They indicate those conditions where the host and device agree as to the direction and amount of data to be transferred. These cases are also referred to as "the thin diagonal."
- Any host or device behavior not specifically outlined in the following sections shall be considered outside this specification and the results are indeterminate.

			HOST	
		Hn	Hi	Ho
	Dn	(1) $Hn = Dn$	( <b>4</b> ) Hi > Dn	( <b>9</b> ) Ho > Dn
E	Di	(2) Hn < Di	(5) H <i>i</i> > D <i>i</i>	
DEVICE			(6) $Hi = Di$	(10) Ho <> Di
DE			( <b>7</b> ) H <i>i</i> < D <i>i</i>	
				(11) Ho > Do
	Do	(3) Hn < Do	(8) H <i>i</i> <> Do	(12) Ho = Do
				( <b>13</b> ) Ho < Do

#### Table 6.1 - Host/Device Data Transfer Matrix

	LEGEND						
Host Expec	Host Expectation						
Hn	Host expects no data transfers						
Hi	Host expects to receive data from the device						
Ho	Host expects to send data to the device						
<b>Device Inte</b>	Device Intent						
Dn	Device intends to transfer no data						
Di	Device intends to send data to the host						
Do	Device intends to receive data from the host						

#### 6.7.1 Hn - Host expects no data transfers

These cases occur when *dCBWDataTransferLength* is zero. This indicates that the host is not expecting to send or receive any data to or from the device.

The general requirements of these cases are:

• The value of the *Direction* bit shall not influence the results of these cases.

The specific host requirements are:

- 1. The host shall send a valid and meaningful CBW.
- The host *may* set or clear the *Direction* bit.
- 2. The host shall attempt to receive a CSW.
- 3. On a STALL condition receiving the CSW, then:
  - The host shall clear the Bulk-In pipe.
  - The host shall attempt to receive the CSW again.
- 4. When the CSW is valid and meaningful, then:
  - [Case (1)]
  - The bCSWStatus = 00h or 01h, and the dCSWDataResidue is 0.
  - [Case (2) or (3)]
    - If bCSWStatus = 02h, then:
      - The host shall Ignore the value of the *dCSWDataResidue*. The host shall Perform a Reset Recovery.

The specific device requirements are:

- 1. The device shall receive a CBW.
- 2. When the CBW is valid and meaningful, then:
  - The device shall attempt the command.

Cases: (1) Hn = Dn

- (2) Hn < Di
- $(3) \quad Hn < Do$

• [Case (1)]

3.

If the device had no data to send or receive, then:

- The device shall set *bCSWStatus* to 00h or 01h.
- The device shall set the *dCSWDataResidue* to 0.
- [Case (2) or (3)] If the device did have data to send or receive, then:
  - The device shall set *bCSWStatus* to 02h.
- The device shall return a valid and meaningful CSW.
- The device may STALL the Bulk-In pipe if bCSWStatus is not 00h or 01h.

# 6.7.2 Hi - Host expects to receive data from the deviceCases:(4) Hi > DnThese cases occur when dCBWDataTransferLength is non zero and the Direction bit(5) Hi > Diis 1 (Data-In). This indicates that the host is expecting to receive data from the(7) Hi < Didevice.(8) Hi < Do

The specific host requirements are:

- 1. The host shall send a valid and meaningful CBW.
- 2. The host shall attempt to receive data from the device.
- 3. On a STALL condition receiving data, then:
  - The host shall accept the data received.
  - The host shall clear the Bulk-In pipe.
- 4. The host shall attempt to receive a CSW.
- 5. On a STALL condition receiving the CSW, then:
  - The host shall clear the Bulk-In pipe.
  - The host shall again attempt to receive the CSW.
- 6. When the CSW is valid and meaningful, then:
  - [Case (4), (5), or (6)]
    - If bCSWStatus = 00h or 01h, then:

The host shall determine the amount of relevant data received from the difference between *dCBWDataTransferLength* and the value of *dCSWDataResidue*.

- [Case (7) or (8)]
  - If bCSWStatus = 02h, then:
    - The host shall ignore the value of the *dCSWDataResidue*.
    - The host shall perform a Reset Recovery.

#### The specific device requirements are:

- 1. The device shall receive a CBW.
- 2. When the CBW is valid and meaningful, then:
  - The device shall attempt the command.
  - [Case (6)]

If the device intends to send *dCBWDataTransferLength*, then: The device shall send *dCBWDataTransferLength* bytes of data. The device shall set *bCSWStatus* to 00h or 01h. The device shall set *dCSWDataResidue* to zero.

• [Case (4)or (5)]

If the device intends to send less data than the host indicated, then:

The device shall send the intended data.

The device may send fill data to pad up to a total of dCBWDataTransferLength.

If the device actually transfers less data than the host indicated, then:

- The device *may* end the transfer with a short packet.
- The device shall STALL the Bulk-In pipe.
- The device shall set *bCSWStatus* to 00h or 01h.
- The device shall set *dCSWDataResidue* to the difference between *dCBWDataTransferLength* and the actual amount of relevant data sent.

#### [Case (7) or (8)] •

If the device either intends to send more data than the host indicated or intends to receive data from the host, then:

The device may send data up to a total of *dCBWDataTransferLength*.

If the device actually transfers less data than the host indicated, then:

- The device may end the transfer with a short packet.
- The device shall STALL the Bulk-In pipe.
- If the device actually transfers *dCBWDataTransferLength* then:

The device may STALL the Bulk-In pipe.

- The device shall set bCSWStatus to 02h.
- 3. The device shall return a valid and meaningful CSW:

#### 6.7.3 Ho - Host expects to send data to the device Cases: (9) Ho > DnThese cases occur when *dCBWDataTransferLength* is non zero-and the *Direction* bit is 0 (Data-Out). This indicates that the host is expecting to send data to the device.

The general requirement of these cases is:

• The host shall not send zero length packets.

The specific host requirements are:

- 1. The host shall send a valid and meaningful CBW.
- 2. The host shall send data to the device.
  - The host shall send a short packet only at the end of the data transfer. •
- 3. On a STALL condition sending data, then:
  - The host shall clear the Bulk-Out pipe.
- 4. The host shall attempt to receive a CSW.
- 5. On a STALL condition receiving the CSW, then:
  - The host shall clear the Bulk-In pipe.
  - The host shall again attempt to receive the CSW.
- 6. When the CSW is valid and meaningful, then:
  - [Case (9), (11), or (12)] •

If bCSWStatus = 00h or 01h, then:

The host shall determine the amount of data that was processed from the difference of dCBWDataTransferLength and the value of dCSWDataResidue.

[Case (10) or (13)] If bCSWStatus = 02h, then: The host shall ignore the value of the *dCSWDataResidue*. The host shall perform a Reset Recovery.

#### The specific device requirements are:

•

- 1. The device shall receive a CBW.
- 2. When the CBW is valid and meaningful, then:
  - The device shall attempt the command.
  - [Case (9), (11), or (12)] •

If the device intends to process less than or equal to the amount of data that the host indicated, then:

The device shall receive the intended data.

The device shall either accept a total of *dCBWDataTransferLength*, or end the transfer prematurely by STALLing the Bulk-Out pipe.

The device shall set *bCSWStatus* to 00h or 01h.

The device shall set dCSWDataResidue to the difference between dCBWDataTransferLength and the actual amount of data that was processed by the device.

[Case (10) or (13)]

If the device either intends to process more data than the host indicated or intends to send data, then:

(10)  $Ho \ll Di$ Ho > Do(11) (12) Ho = Do(13) Ho < Do

The device *may* receive data up to a total of *dCBWDataTransferLength*.

- The device shall either accept a total of *dCBWDataTransferLength*, or end the transfer prematurely by STALLing the Bulk-Out pipe.
- The device shall set *bCSWStatus* to 02h.
- 3. The device shall return a valid and meaningful CSW.
  - The device *may* STALL the Bulk-In pipe if *bCSWStatus* is not 00h or 01h.